

# House Leader's CONSTRUCTION GUIDE





## House Construction Guide

---

# TABLE OF CONTENTS

## Contents

House Construction Guide.....	ii
Chapter 1 - Overview.....	1-1
Resources.....	1-1
Safety.....	1-1
Tools.....	1-1
Green Building.....	1-4
Cleaning and Waste Management.....	1-4
Disposal/Recycle.....	1-4
Recycle Bins.....	1-4
Building Materials.....	1-6
Chapter 2 - Phases of Build.....	2-1
New Build.....	2-1
ReBuild.....	2-1
Coming Soon.....	2-1
Chapter 3 - Foundation.....	3-1
Activities (New Build & Additions).....	3-2
Foundation (Contractor).....	3-2
Utility Taps (Contractor).....	3-2
Interior Drainage (Contractor).....	3-3
Basement Slab Insulation (Volunteers).....	3-3
Temporary Sill Cover (Volunteers).....	3-3
Basement Slab (Contractor).....	3-4
Pour the A/C Pad.....	3-4
Backfill the foundation (Contractor).....	3-4
Caulk Basement Slab (Volunteers).....	3-4
Temporary Power Pole (Contractor).....	3-4
Activities (ReBuild).....	3-5
Foundation Wall Repair (Contractor).....	3-5
Foundation Wall Repair (Volunteer).....	3-5
Foundation Wall Insulation (Volunteers).....	3-5
Interior Drainage & Sump Pump (Optional).....	3-6
Post Pads (Volunteers).....	3-7
Basement Floor (Contractor).....	3-7
Radon (Volunteers).....	3-7
Chapter 4 - First Floor Deck.....	4-1

Activities (New Build & Additions) .....	4-2
Organize Lumber and Trusses .....	4-2
Remove Temporary Sill Cover .....	4-3
Layout Sill Plates.....	4-3
Cut and Drill Sill Plates .....	4-5
Install Sill Sealer.....	4-6
Install Sill Plate.....	4-7
Layout Floor Trusses .....	4-8
Construct the Bearing Wall .....	4-9
Install Floor Trusses.....	4-12
Install Front and Back Band Boards .....	4-16
Install Ribbon Boards.....	4-17
Install Strong-backs .....	4-17
Install Parallel Joist Blocking.....	4-18
Install Decking.....	4-19
Cut Opening for the Stairway.....	4-22
Cut Off Excess OSB .....	4-22
Install Guardrail around the Stairway Opening .....	4-22
Activities (ReBuild).....	4-24
Repair Holes from Chimney Removal .....	4-24
Quality Assurance Checklist .....	4-24
Installing Sill Plate .....	4-24
Installing Floor trusses .....	4-24
Installing Decking .....	4-24
<b>Chapter 5 - First Floor Walls .....</b>	<b>5-1</b>
Activities (New Builds and Additions).....	5-2
Organize the Lumber .....	5-2
Door and Window Headers.....	5-2
Build Bearing Door Frames.....	5-4
Build Non- Bearing Door Frames .....	5-6
Build Bearing Window Frames.....	5-7
Build Non-Bearing Window Frames.....	5-9
Mark the Location of the Exterior Walls .....	5-11
Mark the Location of the Interior Walls .....	5-11
Layout Exterior Wall Panels.....	5-12
Layout Garage Wall Panels .....	5-14
Assemble Exterior Walls .....	5-15
Square Up Framed Walls.....	5-16
Apply OSB.....	5-16

Cut Out OSB at Door / Window Openings.....	5-18
Trim Out Windows and Doors.....	5-19
Erect Exterior Walls .....	5-21
Install Tee Intersection Wall Blocking .....	5-22
String Exterior Walls .....	5-23
Layout and Assemble Interior Walls .....	5-24
Erect Interior Walls.....	5-24
Verify All Walls .....	5-25
Install Double Top Plates .....	5-25
Build Porch Beams .....	5-25
Install Porch Beams.....	5-26
Install Porch Posts for Concrete Porches .....	5-27
Install OSB on Floor Truss Ends and Back Band Boards .....	5-28
Build Temporary Stairs .....	5-28
Activities (ReBuilds).....	5-29
Removing interior walls.....	5-29
Installing new interior walls .....	5-30
Reframing windows & doors.....	5-32
Chapter 6 - Second Floor Deck.....	6-1
Activities.....	6-2
Organize the Lumber .....	6-2
Layout Floor Trusses .....	6-2
Install Floor Trusses.....	6-2
Install Front and Back Band Boards .....	6-2
Install Ribbon Boards.....	6-2
Install Strong-backs .....	6-2
Install Parallel Joist Blocking.....	6-2
Install Decking.....	6-2
Cut off the Excess OSB .....	6-2
Cut Opening for the Stairway.....	6-2
Cut Off Excess OSB .....	6-2
Install Guardrail around the Stairway Opening.....	6-2
Chapter 7 - Second Floor Walls .....	7-1
Activities.....	7-2
Organize the Lumber .....	7-2
Build Window Headers.....	7-2
Build 2 <sup>nd</sup> Floor Door Frames .....	7-2
Build 2 <sup>nd</sup> Floor Bearing Window Frames.....	7-2
Build 2 <sup>nd</sup> Floor Non-Bearing Window Frames.....	7-2

Mark the Location of the Exterior Walls .....	7-2
Mark the Location of the Interior Walls .....	7-2
Layout Exterior Wall Panels.....	7-2
Assemble Exterior Walls .....	7-2
Square up Framed Walls .....	7-2
Apply OSB.....	7-2
Cut Out OSB at Windows Openings .....	7-2
Trim Out Windows.....	7-2
Erect Exterior Walls .....	7-2
Install Tee Intersection Wall Blocking .....	7-2
String Exterior Walls .....	7-2
Layout and Assemble Interior Walls .....	7-3
Erect Interior Walls.....	7-3
Verify All Walls .....	7-3
Install Double Top Plates .....	7-3
Install OSB on Floor Truss Ends and Back Band Boards .....	7-3
Quality Assurance Checklist .....	7-3
<b>Chapter 8 - Roof Framing .....</b>	<b>8-1</b>
<b>Activities (New Builds and Additions).....</b>	<b>8-2</b>
Set Bathtub .....	8-2
Prepare House Roof Gable Trusses.....	8-2
Layout Roof Trusses.....	8-8
Install Strong-back Bracing.....	8-11
Set Main Roof Trusses .....	8-12
Install Sub-fascia Boards .....	8-15
Install Truss Heel Sheathing.....	8-16
Prepare Porch Gable Roof Trusses.....	8-17
Install Porch Roof Trusses.....	8-19
Install Porch Sub-Fascia .....	8-20
Prepare Garage Gable Roof Truss.....	8-20
Layout Garage Roof Trusses.....	8-22
Install Garage Strong-Back Bracing .....	8-22
Install Garage Roof Trusses .....	8-22
Install Garage Sub-Fascia .....	8-22
Sheet Roof .....	8-22
Install Cat Walks .....	8-24
Install Wind Bracing .....	8-25
Install Hurricane Clips .....	8-25
Planning for Transition Roofs.....	8-25

Prepare Transition Trusses.....	8-26
Planning for Intersecting Roofs.....	8-28
Install Valley Framing.....	8-28
Activities (ReBuilds).....	8-34
Build up Roof for Insulation.....	8-34
Quality Assurance Checklist.....	8-35
Chapter 9 - Roofing .....	9-1
Activities.....	9-2
Setup up the Ladder .....	9-2
Supply the Roof with Shingles .....	9-2
Apply Drip Edge Along Lower Edge of the Roof.....	9-4
Apply Ice and Water Shield.....	9-5
Apply Felt Paper.....	9-6
Install Drip Edge on the Rake Edge.....	9-6
Install Sub-Flashing .....	9-7
Install Dow Board on the Vertical Walls.....	9-7
Install the Starter Course .....	9-7
Set Reference Lines .....	9-8
GAF Instructions for Timberline Dimensional Shingles .....	9-8
Install the Shingles.....	9-10
Replace Fall Protection.....	9-11
Valley Construction - Woven Valley.....	9-12
Install Step Flashing.....	9-13
Install Apron Flashing .....	9-14
Covering the Peak .....	9-15
Install Ridge Vents.....	9-16
Remove the Fall Protection.....	9-18
Quality Assurance Checklist.....	9-19
Chapter 10 - Pump Jacks .....	10-1
Set Pump Jack Brackets.....	10-1
Set Pump Jack Poles.....	10-2
Attach Pump Jacks .....	10-2
Set Walk Boards .....	10-3
Set the Safety Boards .....	10-3
Quality Assurance Checklist.....	10-3
Chapter 11 - Porch Framing & Trim .....	11-1
Activities.....	11-2
Concrete Porches (Contractor).....	11-2
Wooden Porches (Volunteers).....	11-2

Wrap Porch Beams (Volunteer) .....	11-6
Wrap the Porch Posts (Volunteer) .....	11-8
Install the Porch Railings (Volunteer) .....	11-9
Install Porch Skirting .....	11-13
Quality Assurance Checklist .....	11-15
Chapter 12 - Exterior Dow Board .....	12-1
Apply Dow Board to Exterior .....	12-1
Tape the Seams .....	12-3
Quality Assurance Checklist .....	12-3
Chapter 13 - Windows and Doors .....	13-1
Activities (New Builds & Additions) .....	13-1
Verifying Windows and Doors Orders .....	13-1
Installing Windows .....	13-2
Egress Windows (Volunteers) .....	13-5
Installing Exterior Doors .....	13-6
Install Door Hardware .....	13-8
Activities (ReBuilds) .....	13-8
Glass Block Windows (Contractor) .....	13-8
Install Door Kick Plates .....	13-9
Quality Assurance Checklist .....	13-9
Chapter 14 - Stairs & Finish Framing .....	14-1
Activities .....	14-2
Install Stairway Landings .....	14-2
Install Stairs .....	14-2
Install Framing for Stairway Ceiling .....	14-2
Install Storage Area over Stairway .....	14-3
Install Blocking .....	14-3
Install Kitchen Cabinet Blocking .....	14-4
Install Range Hood Blocking .....	14-4
Install Bathroom Blocking .....	14-4
Install Handrail Blocking .....	14-4
Install Door Handle Blocking .....	14-5
Remove Bottom Plate in Doorways .....	14-5
Install Attic Access .....	14-5
Build Basement Shelves .....	14-6
Install Basement Safety Rails .....	14-7
Install the Bath Tub Enclosure .....	14-9
Quality Assurance Checklist .....	14-10
Chapter 15 - Siding .....	15-1

Activities.....	15-2
Organize Materials .....	15-2
Vinyl Siding Parts .....	15-2
Set Up a Cutting Area .....	15-3
Install F-channel for soffit panels .....	15-4
Gable Soffit Joint Cover .....	15-5
Install Soffit Panels .....	15-6
Cover Fascia and Cornices.....	15-8
Mark the Starting Lines .....	15-10
Create a Reference Line .....	15-11
Install Siding Blocks (Contractors).....	15-12
Install Foundation Wall Covering .....	15-12
Install Outside / Inside Corners.....	15-12
Install J channel .....	15-13
Install utility trim strips (P-channel) .....	15-16
Install Starter Strips.....	15-17
Install Gable Vent (If Provided) .....	15-17
Install siding panels.....	15-17
Shakes (If Provided) .....	15-23
Install Shutters (If Provided).....	15-24
Quality Assurance Checklist.....	15-25
<b>Chapter 16 - Gutters, Downspouts, and Conductor Lines ...</b>	<b>16-1</b>
Activities.....	16-2
Install Gutters and Downspouts (Contractor).....	16-2
Install Conductor Lines (Volunteers).....	16-2
Install Gutter Guards (Volunteers).....	16-2
<b>Chapter 17 - Rough-in Mechanicals.....</b>	<b>17-1</b>
Activities.....	17-1
HVAC Rough-In (Contractor).....	17-1
Plumbing Top-out (Contractor) .....	17-1
Radon Passive System (Contractor).....	17-2
Seal the Sewer (Volunteers).....	17-2
Basement Floor Sealing (Volunteers).....	17-2
Electrical Rough-In (Contractor) .....	17-2
Phone Jack (Contractor) .....	17-2
Cable Connection (Contractor) .....	17-2
Mark the Electric Boxes (Volunteers) .....	17-2
Spray Paint the Cold Air Return (Volunteers).....	17-3
<b>Chapter 18 - Insulation .....</b>	<b>18-1</b>

Activities.....	18-2
Seal the Bottom Plates .....	18-2
Seal the Plates and Subflooring.....	18-2
Insulate Walls.....	18-2
<b>Insulate Band Boards between First and Second Floors</b> .....	18-5
Insulate Around Windows and Doors .....	18-5
Insulate the Drywall Penetrations in the Attic .....	18-5
Install Positive Ventilation Chutes (Cardboard Baffles).....	18-5
Insulating the Attic.....	18-6
Insulate Band Boards in the Basement .....	18-6
Insulate Beam Pockets in the Basement .....	18-7
Cutting Non-Faced Insulation .....	18-7
<b>Chapter 19 - Drywall .....</b>	<b>19-1</b>
Activities.....	19-2
Organizing Materials / Areas (Optional).....	19-2
Drywall Stops (Volunteers) .....	19-2
Apply Drywall (Optional) .....	19-3
Prepare an Attic Access Cover (Volunteers) .....	19-6
Prepare for the Finishers (Optional).....	19-7
Finish the Drywall (Contractor) .....	19-7
Cleanup after the Finishers (Volunteers) .....	19-7
Installing Drywall Screws .....	19-7
Cutting Drywall.....	19-8
Moving Drywall.....	19-8
Making Cut Outs in the Drywall.....	19-8
<b>Chapter 20 - Painting.....</b>	<b>20-1</b>
Activities.....	20-2
Interior Walls .....	20-2
Interior Trim.....	20-3
Basement Steps.....	20-4
Exterior Doors .....	20-4
Exterior Trim.....	20-4
<b>Chapter 21 - Flooring.....</b>	<b>21-1</b>
Activities – Vinyl Flooring .....	21-2
Install Vinyl Flooring Underlayment (Luaun).....	21-2
Install Vinyl Flooring.....	21-3
Activities – Laminate Flooring .....	21-4
Acclimate the Flooring .....	21-4
Plan your work .....	21-5

Installing the Underlayment .....	21-5
Install Laminate Flooring .....	21-5
Install Thresholds .....	21-6
Quality Assurance Checklist .....	21-6
Chapter 22 - Cabinets & Vanities .....	22-1
Activities .....	22-2
Layout Cabinets .....	22-2
Prepare Wall Units .....	22-2
Install Wall Units .....	22-3
Prepare Base Units .....	22-3
Install Base Units .....	22-3
Reinstall and Adjust Doors .....	22-4
Reinstall and Adjust Drawers .....	22-4
Install Shelves .....	22-4
Install Cabinet Knobs .....	22-5
Install Countertops .....	22-5
Prepare Vanities .....	22-5
Install Vanities .....	22-5
Install Vanity Knobs .....	22-6
Install Sink Tops .....	22-6
Quality Assurance Checklist .....	22-6
Chapter 23 - Interior Doors & Trim .....	23-1
Activities .....	23-2
Order Doors (Supervisor / Project Lead) .....	23-2
Order Window Sills (Supervisor / Project Lead) .....	23-2
Organize Materials .....	23-2
Install Interior Doors .....	23-2
Install Door Casing .....	23-3
Install Bypass Doors .....	23-4
Install the Baseboard Trim .....	23-5
Install Shoe Molding .....	23-6
Back Caulk Trim .....	23-7
Install Marble Sills .....	23-9
Install the Window Trim .....	23-9
Install Quarter Round at Bathtub .....	23-9
Install Quarter Round at Exterior Doors .....	23-9
Install the Kneewall Caps .....	23-9
Install the Handrails .....	23-10
Install Attic Access Cover .....	23-11

Stain and Polyurethane the Trim .....	23-11
<b>Chapter 24 - Finishing Mechanicals .....</b>	<b>24-1</b>
<b>Activities.....</b>	<b>24-1</b>
Final HVAC (Contractor) .....	24-1
Install A/C Cage (Volunteers) .....	24-1
Finish Plumbing (Contractor) .....	24-1
Finish Electrical (Contractor).....	24-2
<b>Chapter 25 - Interior Finishes .....</b>	<b>25-1</b>
<b>Activities.....</b>	<b>25-2</b>
Install Bathroom Accessories.....	25-2
Install Shelving .....	25-3
Install Door Hardware .....	25-3
Caulk beneath the Window Sills .....	25-4
Install the Mini Blinds .....	25-5
<b>Chapter 26 - Walkways, Driveway, and Parking Pad .....</b>	<b>26-1</b>
<b>Chapter 27 - Landscaping and Exterior Finishes .....</b>	<b>27-1</b>
<b>Activities.....</b>	<b>27-1</b>
Install House Numbers.....	27-2
Install Screen Doors.....	27-2
Install Final Grade .....	27-3
Install the Mail Box.....	27-3
Prepare Area for Landscaping Plants .....	27-3
Plant the Plants .....	27-4
Mulch the plant area .....	27-4
Prepare Lawn Area .....	27-4
Install Stepping Stones .....	27-4
Spread Grass Seed .....	27-5
Water Plants and Seed .....	27-5
Quality Assurance Checklist .....	27-5
<b>Chapter 28 - Carpeting .....</b>	<b>28-1</b>
<b>Activities.....</b>	<b>28-1</b>
Clean the Floor and Stairs (Volunteers) .....	28-1
Lay the Carpeting (Contractor) .....	28-1
Install the Carpet Shield (Volunteers) .....	28-1
<b>Chapter 29 - Cleanup .....</b>	<b>29-1</b>
<b>Activities.....</b>	<b>29-1</b>
Clean the Kitchen.....	29-1
Clean the Windows .....	29-2
Install the Window Screens.....	29-2

Clean the Bathrooms .....	29-2
Clean Light Fixtures .....	29-2
Clean Porches.....	29-2
Quality Assurance Checklist .....	29-2
Chapter 30 - Punch List .....	30-1
Activities.....	30-1
Chapter 31 - Appliances .....	31-1
Activities.....	31-1
Install Stove.....	31-1
Install Refrigerator.....	31-1
Install Dishwasher.....	31-1
Install Dehumidifier .....	31-2
Quality Assurance Checklist .....	31-2
Chapter 32 - Garage.....	32-1
Activities.....	32-2
Foundation .....	32-2
Walls .....	32-2
Roof Framing .....	32-3
Roofing.....	32-4
Exterior Dow Board .....	32-4
Doors.....	32-4
Siding .....	32-4
Gutters .....	32-4
Painting .....	32-5
Shelving .....	32-5
Quality Assurance Checklist .....	32-5
Appendix .....	32-i
Glossary .....	32-i

## TABLE OF FIGURES

Gantt Chart.....	2-2
Figure 3.1 – Foundation .....	3-1
Figure 3.2a Basement Slab Insulation .....	3-3
Figure 3.2b Basement Slab Insulation .....	3-3
Figure 3.3 - Foundation Dow & Cap .....	3-4
Figure 3.4 - Dow Clip Strips .....	3-6
Figure 4.1 - Crown the Lumber .....	4-3
Figure 4.2 - Sill Plate and Floor Truss Systems .....	4-4
Figure 4.3 – Sill Plate Reference Lines.....	4-5
Figure 4.4 - Marking the sill plate .....	4-6
Figure 4.5 - Sill Sealer.....	4-7
Figure 4.6 - Attaching the Sill Plate.....	4-8
Figure 4.7 – Laying out the trusses.....	4-9
Figure 4.8 - Marking the Bearing Wall Top Plate .....	4-11
Figure 4-9 - Girder Trusses.....	4-13
Figure 4.10 - Section of Floor Trusses.....	4-14
Figure 4.11 - Floor Trusses on a Bearing Wall .....	4-15
Figure 4.12 - LVL Joist Hangers .....	4-16
Figure 4.13 – Strong-Back Blocking .....	4-18
Figure 4.14 - I-Joists .....	4-19
Figure 4.15 - Decking Layout.....	4-20
Figure 4.16 – Guard Rails .....	4-23
Figure 5.1 – Load Bearing Header.....	5-3
Figure 5.2 - Non-Load Bearing Header.....	5-4
Figure 5.3 – Load Bearing Door Frame .....	5-5
Figure 5.4 – Non-Load Bearing Door Frame .....	5-7
Figure 5.5 – Load Bearing Window Frame .....	5-9
Figure 5.6 – Non-Load Bearing Window Frame .....	5-11
Figure 5.7 – Two Stud Corner.....	5-12
Figure 5.8 – Window and Door Layout .....	5-13
Figure 5.9 - Plate Layout.....	5-14
Figure 5.10 - Beam Pocket .....	5-15
Figure 5.11 - Paneling Exterior Walls .....	5-18
Figure 5.12 – Exterior Window Trim .....	5-20
Figure 5.13 – Exterior Door Trim .....	5-20
Figure 5.14 – Tee Wall Intersection Blocking .....	5-23
Figure 5.15 – Stringing the Wall.....	5-24
Figure 5.16 - Beam Construction .....	5-26
Figure 5.17 – Temporary Stairs .....	5-29
Figure 5.18 – Replacing Interior walls.....	5-31
Figure 8.1 – Nailer on Gable Truss.....	8-4
Figure 8.2 – Rake on House Gable Truss .....	8-5
Figure 8.3 - House Cornice Return – Elevation View .....	8-6
Figure 8.4 - House Cornice Return - Isometric View .....	8-7
Figure 8.5 - Dow on House Gable Truss .....	8-8
Figure 8.6 - Aligning the Roof Trusses .....	8-10
Figure 8.7 – Strong-back.....	8-11
Figure 8.8 – Short Common Truss Support.....	8-13
Figure 8.9 – Diagonal Common Truss Supports .....	8-14

Figure 8.10 – Sub-fascia & Soffits .....	8-16
Figure 8.11 - Preparing Porch Gable Trusses .....	8-18
Figure 8.12 – Porch Cornice Return .....	8-19
Figure 8.13 - Garage Cornice Return .....	8-22
Figure 8.14 – Ridge Vent Cutout .....	8-24
Figure 8.15 – Hurricane Clips .....	8-25
Figure 8.16 - Intersecting Roofs.....	8-28
Figure 8.17 – Valley Ridge Layout.....	8-29
Figure 8.18 – Valley Framing.....	8-30
Figure 8.19 – Valley Ridge Installation .....	8-31
Figure 8.20 – Valley Jack Rafter Layout.....	8-32
Figure 8.21 – Valley Jack Rafters .....	8-33
Figure 8.22 – Roof Structure of Insulation .....	8-34
Figure 9.1 - Drip Edge.....	9-4
Figure 9.2 - First Course of Shingle.....	9-11
Figure 9.3 – First Shingle Sizes .....	9-11
Figure 9.4 – Woven Valley Shingles .....	9-13
Figure 9.5 – Step Flashing.....	9-14
Figure 9.6 – Apron Flashing.....	9-15
Figure 9.7 – Ridge Vent Profile.....	9-17
Figure 9.8 – Coravent Ridge Vent Installation Instructions.....	9-18
Figure 11.1 Porch Ledger .....	11-3
Figure 11.2 – Porch Framing .....	11-5
Figure 11.3 - Wrapping Headers.....	11-6
Figure 11.4 - Smart Trim on Porch Beam .....	11-8
Figure 11.5 - Post Wrap.....	11-9
Figure 11.6 – Baluster Layout (Odd Number of Balusters).....	11-12
Figure 11.7 - Baluster Installation .....	11-12
Figure 11.8 - Porch Skirting (Front of Porch).....	11-14
Figure 11.9 – Porch Skirting (Side of Porch) .....	11-15
Figure 12.1 - Dow Board Installation.....	12-2
Figure 13.1 – Home Guard Installation before installing the Window.....	13-3
Figure 13.2 – Home Guard Installation after Installing the Window .....	13-5
Figure 13.3 – Door Sealing .....	13-8
Figure 14.1 – Hand Rail Blocking .....	14-5
Figure 14.2 – Basement Storage Shelves .....	14-7
Figure 14.4 – Safety Railing.....	14-9
Figure 15.1 – Siding Jig .....	15-4
Figure 15.2 – Soffit Joint Cover at the Peak .....	15-6
Figure 15.3 – Soffit under Cornice Returns .....	15-7
Figure 15.4 – Nailers for Soffit Panels .....	15-8
Figure 15.6 – Corner Posts .....	15-13
Figure 15.7 – J-Channel on Doors.....	15-15
Figure 15.8 – J-Channel below Porch Roof.....	15-16
Figure 15.9 – Fitting Siding under the Gable .....	15-21
Figure 16.1 – Conductor Lines Layout.....	16-3
Figure 17.1 - Electrical box symbols .....	17-3
Figure 18.1 – Netting Installation .....	18-4
Figure 18.2 – Stapling the Netting .....	18-4
Figure 18.3 – Filling the Cavities.....	18-5
Figure 18.4 – Ventilation chutes .....	18-6
Figure 23.2 – Baseboard Trim for Stairways .....	23-8
Figure 32.1 – Overhead Garage Door Framing.....	32-3